

MAHARSHI DAYANAND UNIVERSITY ROHTAK

NOTICE INVITING TENDER

Sealed tenders on percentage basis are invited on behalf of the Registrar, MDU, Rohtak from contractors/societies / agencies on approved list of Haryana PWD B&R / P.H. Br., MES, CPWD, autonomous bodies and other State / Centre Govt. undertakings. The tender forms will be issued to the contractors / societies / agencies up to the date of opening of tenders as mentioned against work by 12:00 Noon and will be received upto 2:00 P.M. in the office of the Registrar and opened at 2:30 P.M. on the same day in the Committee Room of Vice-Chancellor office in the presence of the tenderers or their authorized representatives, who may like to be present at that time. **The tender documents may be obtained from the office of the undersigned and the same be deposited in the office of the Registrar by the due date.**

Sr. No.	Name of work	App. Amt. (Rs.)	Earnest Money (Rs.)		Cost of tender form (Rs.)	Date of opening of tender	Time limit
			Society	Contractor			
1.	Development of Cricket ground and Hockey Ground in Sports Complex	69,00,000/-	69,000/-	1,38,000/-	5,000/-	24.02.2012	05 months
2.	Supplying and filling tibba sand in various places in MDU Campus	50,00,000/-	50,000/-	1,00,000/-	5,000/-	24.02.2012	04 months

CONDITIONS:-

1. Complete NIT / DNIT (Detailed Notice Inviting Tender) alongwith eligibility criteria/terms & conditions and changes if any can be seen in the office of undersigned on any working day during office hours (9:00 AM to 5:00 PM) and on University Website – www.mdurohtak.ac.in
2. The tenderer will keep in touch with the University Web site for any change in the NIT / DNIT till the last date/revised last date of sale of tender and incorporate such changes in NIT / DNIT and the tender bids.
3. At the time of purchase of tenders, the contractors should bring with them, proof of enlistment with copy of PAN card and one successfully work done certificate (similar nature) of 80% of the estimated cost of this tender during the last five years (Financial Year 2006-07 to 2010-11) or two successfully work done certificates (similar nature) of 60% of the estimated cost of this tender during the last five years (Financial Year 2006-07 to 2010-11) or three successfully work done certificate (similar nature) of 40% of the estimated cost of this tender during the last five years (financial year 2006-07 to 2010-11) Copy of latest income tax return will also be submitted. All these certificates / documents should be submitted duly self attested with stamp.
4. In case tendering day happens to be a holiday, the tenders will be received / opened on next working day at the same time.
5. Earnest money is to be deposited at the time of purchase of the tender. It should be in the shape of Demand Draft or Deposit at Call in favour of the Executive Engineer, MDU, Rohtak payable at Rohtak.

6. Contractors shall quote single percentage of rate below/above on (HSR+C.P. as on Nov. 2011) on all chapters. N.S. item rates are to be quoted separately. The tender, without the rates of N.S. items, if any, in DNIT, will be rejected.
7. Conditional tender is liable to be rejected.
8. Any work, here tendered, may be withdrawn from further processing at any stage at the discretion of the competent authority without assigning any reason.
9. Engineer-in-Charge is competent to increase / decrease the quantity of work. In case of decrease of quantity, the contractor shall have no claim to any payment or compensation whatsoever on account of any profit or advantage which he might have derived from the execution of the work in full.
10. Nothing extra whatsoever shall be paid on account of losses, damages done by rains or any other natural calamity.
11. The tender is liable to be rejected if the tender is found in variance of the above conditions or the conditions of the DNIT.
12. The University reserves the right to accept or reject or negotiate any of the tender or conditions/items without assigning any reason.
13. Plumbing and E.I. work shall be got done through license holder agencies for the works involving PH / E.I.
14. The agencies shall paste the cello tape on the rates quoted by them.

Executive Engineer

Endst. No. EE/ 2012 / 790-830

Dated: 01.02.2012

A copy of the above is forwarded to the following for information and necessary action:-

1. Superintending Engineer, PWD B&R Circles, Rohtak
2. Technical Advisor to VC, MDU, Rohtak
3. Executive Engineer, PWD B&R (Medical College), Rohtak
4. Executive Engineer, KUK / HAU. Hisar / GJU, Hisar / CDLU, Sirsa
5. Secretary to Vice-Chancellor (for kind information of the Vice-Chancellor), M. D. University, Rohtak
6. P.A. to Registrar (for kind information of Registrar), MDU, Rohtak
7. SDE(C-I, II, III) / SDE (E-I) / SDE (PH) / SDE (Horti.-I, II), MDU, Rohtak
8. Divisional Accountant / H.D.M., Engineering Cell, MDU, Rohtak
9. Notice Board
10. Contractor/Agency/Society:_____

Executive Engineer

DNIT for the work "Development of Cricket Ground and Hockey Ground in Sports Complex in MDU, Rohtak"

App. Amt. Rs. 69.00 lac
 Earnest Money Rs. 1,38,000/- / Rs. 69,000/-
 Time Limit: 05 months

Sr. No. / HSR	Qty.	Description	Rate (Rs.)	Unit
1/6.6	861 cum	Earth work in excavation in foundations, trenches, etc in all kinds of soils, not exceeding meters depth including dressing of bottom and sides of trenches, stacking the excavated soil, clear from the edge of excavation and subsequent filling around masonry, in 15 cm layers with compaction, including disposal of all surplus soil, as directed with in a leadoff 30 meters	@ Rs. 1108.10 (Rs. One thousand one hundred eight & paisa ten only)	Per % cum
2/10.26	343 cum	Cement concrete 1:8:16 with brick ballast 40 mm nominal size in foundation and plinth (see note 2 at page 4)	@ Rs. 300.20 (Rs. Three hundred & paisa twenty only)	Per cum
3/11.22	421 cum	1 st class brick work 1:6 (1 cement : 6 stone dust) (see note 1 at page 4)	@ Rs. 413.55 (Rs. Four hundred thirteen and paisa fifty only)	Per cum
4/15.5	1290 sqm	12 mm thick cement plaster 1:4	@ Rs. 12.70 (Rs. Twelve & paisa seventy only)	P.sqm
5/15.75	2334 sqm	Cement rendering on paster 1mm thick	@ Rs. 4.25 (Rs. four and paisa twenty five only)	Per sqm
6/11.24	515 cum	First class brick work laid in cement, stone dust (from crusher) mortar 1:4 in foundation and plinth (see note 1 at page 4)	@ 444.65 (Rs. four hundred forty four and paisa sixty five)	Per cum

Contd...P/2....

Sr. No. / HSR	Qty.	Description	Rate (Rs.)	Unit
7/24.1	168 sqm	Preparation of sub grade including trenching, rough dressing of spoil, final dressing of earth, to given levels and chamber, watering, rolling with road roller, and compacting the bed.('b' type)	@ Rs. 92.45 (Rs. ninety two and paisa forty five only)	Per 100 sqm
8/10.132 + 10.95(a)	25 cum	Cement concrete 1:1 ½ :3 with stone aggregate 20mm nominal size in pavement, roads, taxi-tracks and run ways, laid to required slope and camber, including consolidation, finishing and tamping complete (a) extra over item nos. 10.79 to 10.94, if 1: 1½:3 mix is used instead of 1:2:4	@ Rs. 729.30 (Rs. seven hundred twenty nine and paisa thirty only)	Per cum
9/10.81 + 10.95(a)	29 cum	Cement concrete 1:1.1/2:3 with stone aggregate 20mm nominal size for reinforced concrete work in Shelves excluding steel reinforcement, but including centering and shuttering, laid in position, complete in all respects. (a) extra over item nos. 10.79 to 10.94, if 1: 1½:3 mix is used instead of 1:2:4	@ Rs. 1034.60 (Rs. one thousand thirty four and paisa sixty only)	Per cum
10/14.8	1044 sqm	Conglomerate floor 25 mm thick cement concrete topping 1:2:4	@ Rs.22.40 (Rs. twenty two and paisa forty only)	Per Sqm

Contd...P/3....

Sr. No. / HSR	Qty.	Description	Rate (Rs.)	Unit
11/18.12	5 qtl.	Wrought iron and mild steel (using angles, flats, square bars, tees and channels) ladders, grills, grating frames, window guard , iron doors openable or fixed stair case or parapet or any other type of railing , gates and tree guards etc., including cost of screws and welding rods or bolts and nuts complete fixed in position	@ Rs. 1,040.35 (Rs. One thousand forty & paisa thirty five only)	P.qtl
12/10.78 + 10.95 (a)	4 cum	Precast cement concrete 1: 1½ :3 with stone aggregate 20mm nominal size in tiles and channels and the like items, finished smooth with 6mm thick cement plaster 1:3 on exposed surface including form work, placing and fixing in position, complete at the ground level or in first storey. (a) extra over item nos. 10.79 to 10.94, if 1: 1½:3 mix is used instead of 1:2:4	@ Rs. 1,112.05 (Rs. one thousand one hundred twelve and paisa five only)	Per cum
13/18.22	40 qtl.	Cold twisted deformed (ribbed/tor steel) bars for RCC works where not included in the complete rate or RCC including bending binding and placing in position complete	@ Rs. 917.05 (Rs. Nine hundred seventeen & paisa five only)	Per qtl.
14/NS	5000 cum	Excavation of earth / rubbish material and disposal within the campus including loading and unloading etc. complete as per entire satisfaction of Engineer-in-Charge.	Rate to be quoted by the contractor	Per cum
15/NS	29625 cum	Earth filling (tibba sand) free from vegetation and rock etc. brought from outside with irrespective of lead from source of earth to site of work including all lead and lift and laying in 15 cm layers including ramming, watering and consolidation, rolling and compaction of earth. The successive layer of earth should not be provided until and unless layer under construction is thoroughly compacted and watered. The complete rate quoted by the contractor shall take into account all allowances for labour, hardness, wetness and all kind	Rate to be quoted by the contractor	Per cum

Contd....P/4....

Sr. No. / HSR	Qty.	Description	Rate (Rs.)	Unit
		of carriage, loading, unloading, total lead and lift of soil involved to the entire satisfaction of Engineer-in-Charge conforming fully to specification no. 6.2 and 6.3 of Haryana PWD specification 1990 including subsequent Agenda and Corrigenda issued from time to time		
16/NS	52 mtr.	Providing and placing in position 110mm dia PVC pipe (ISI mark) 4 kg. per sqcm pressure including necessary cutting and wastage etc. complete as per entire satisfaction of Engineer-in-Charge.	Rate to be quoted by the contractor	Per mtr.

- Note:
- i) Old bricks will be issued by the Department @ Rs.3500/- per thousand from various sites of MDU Campus, Rohtak.
 - ii) Brick bats for brick ballast will be issued by the Department @ Rs. 450/- per cum from various sites of MDU Campus, Rohtak

DNIT for the work "Supplying and filling tibba sand in various places in MDU Campus, Rohtak"

App. Amt. Rs. 50.00 lac
 Earnest Money Rs. 1,00,000/- / Rs. 50,000/-
 Time Limit: 04 months

Sr. No. / HSR	Qty.	Description	Rate (Rs.)	Unit
1/NS	26518 cum	Earth filling (tibba sand) free from vegetation and rock etc. brought from outside with irrespective of lead from source of earth to site of work including all lead and lift and laying in 15 cm layers including ramming, watering and consolidation, rolling and compaction of earth. The successive layer of earth should not be provided until and unless layer under construction is thoroughly compacted and watered. The complete rate quoted by the contractor shall take into account all allowances for spreading, ramming, wetness, consolidation, compaction and all kind of carriage, loading, unloading, total lead and lift of soil involved to the entire satisfaction of Engineer-in-Charge conforming fully to specification no. 6.2 and 6.3 of Haryana PWD specification 1990 including subsequent Agenda and Corrigenda issued from time to time	Rate to be quoted by the contractor	Per cum
2/NS	8839 cum	Earth filling (tibba sand) free from vegetation and rock etc. brought from outside with irrespective of lead from source of earth to site of work including all lead and lift and spreading at site. The complete rate quoted by the contractor shall take into account all allowances for carriage, loading, unloading, total lead and lift of soil involved to the entire satisfaction of Engineer-in-Charge.	Rate to be quoted by the contractor	Per cum
3/NS	9167 cum	Excavation of earth / rubbish material and disposal within the campus including loading and unloading etc. complete as per entire satisfaction of Engineer-in-Charge.	Rate to be quoted by the contractor	Per cum