

**University Computer Centre**

**Subject: Notice for inviting sealed Quotations for purchasing of IT equipments**

The University Computer Centre required following IT equipments make 'D' Link/HP/strelie etc.)

*DSno - UCC/411-45  
24.3.14*


Sr.No.	Name of Items	Qty.	Estimated Cost
1.	<b>24 Core SM Optical Fibre cable</b> Fiber Type : 9/125µm (OS1) singlemode, Jacket with Corrugated steel armor, Water blocking, Operating temp-40° to 70°C, Attenuation Singlemode: 0.40dB/km @ 1310nm; 0.30dB/km @ 1550nm	600 mtr	
2.	<b>6 Core SM optical Fibre Cable</b> Fiber Type : 9/125µm (OS1) singlemode, Jacket with Corrugated steel armor, Water blocking, Operating temp-40° to 70°C, Attenuation Singlemode: 0.40dB/km @ 1310nm; 0.30dB/km @ 1550nm	900 mtr	
3.	<b>Concrete Chamber</b> Making of RCC , 4 feet diameter in round shape with cover , Water Proff ,Hight is 3 feet.	4	
4.	<b>Universal Jointing Consortium</b> 24f*3 fiber termination support, three 30mm size rubber grommets, Water Proof, Solid plastic material which have dust not effect.	4	
5.	<b>LIU</b> 24 port, Rack Mount min. 1u thick, all metal body construction, Lockable, 24 S.M. duplex SC adapters ,Accessories: Mounting hardware and fiber routing accessory kit included; contains 2 fiber management spools, two 30mm size rubber grommets, one cable gland, Cable Ties and #12-24 and M6 x 1 mounting screws.	4	

6.	<b>Concrete route marker</b> Make of Rcc Min. 3 iron Saria, Pole type marker, dimensan of 150 mm *100mm hight 3.5 feet	15	
7.	<b>Cat 6 UTP cable Roll (305 mtr)</b> 4 Pair 23 awg 350MHZ ETL/UL Verified as per EIA/TIA-568 B.2 ,N/W Support 1000Mbps, Material solid bare copper, polythylene Insulation, operating temp - 20C to 60C	8	
8.	<b>24 Port L2 Managed Switch</b> 1000 Mbps RJ45 Ethernet 24 ports, Manged with Ip address, CLI & GUI Configuration with Web & telnet based, support min. 50 Vlan,Rack Mountable with proper accessories.Should have Flash ROM of 32MB or more.Should have DRAM of 256MB or more.Should support STP instances.Should support 802.1p Quality of Service (QoS) with Strict Priority (SP), Weighted Round Robin (WRR)	11	
9.	<b>Cat 6 STP Cable Roll (305 mtr)</b> 4 Pair 23 awg 350MHZ ETL/UL Verified as per EIA/TIA-568 B.2 , N/W Support 1000Mbps, Material solid bare copper, polythylene Insulation, operating temp - 20C to 60C , 0.5 MM TIN COPPER DRAIN WIRE & ALUMINIUM / POLYSTER TAPE.NOMINAL 0.50 MM THICK PVC COATING	3	
10.	<b>12U rack</b> Single Section Unit, Rigid frame that can be fixed to the wall, Top and bottom cable entry facility, Front section with glass door and lock, min. load Rating 15 kg, 600mm wide x 500mm deep,	3	
		<b>Total:</b>	

You are requested to kindly quote your rates for the same. Terms and conditions for quoting the rates are given below-

1. All charges payable by the University should clearly be stated.

2. The quotation should be submitted only if the material is available in your ready stock and can be provided within one month. The supplier should be an having PAN India License.
3. Sealed quotation should reach the office of the undersigned by name on/before 28.03.2014 at 3:30 pm quoting our reference and due date of opening on the envelope. The quotations will be opened at 4.00 pm on the same day.
4. Quantities specified may increase or decrease.
5. The acceptance of goods is subject to the approval of Inspection Committee.
6. If your rates are approved by DGS&D and other Central/State Agency, the same must be mentioned and the copy of the contract be attached.
7. Dispute, if any, will be subject to Rohtak Jurisdiction.
8. The University reserves the right to reject any or all quotations without assigning any reason thereof.

  
28/3/14  
Director, UCC